


## MAXI-STACK® IV

The Maxi-Stack® IV car is the ideal domestic doublestack container car because it provides the optimum balance between tare weight and capacity.

It is a three-unit articulated double-stack car that can handle containers from 20' to 53' long in the well and containers from 40' to 57' in the top position. The Maxi-Stack IV utilizes 70-ton end trucks and 125-ton intermediate trucks.



DIMENSIONS per 3-unit car (Approximate)			
Length over couplers	203' 93/4"	Height, extreme (loaded*)	20' 3"
Length, between truck centers, end unit	63'1"	Width, over side sills	9'10 9/16"
Length, between truck centers, intermediat	e unit 63' 6"	Width, extreme	10'8"
Height, top of rail to top of side sill	5'0"	Well size, end unit	53' x 102 3/8"
Height, rail to support surface (empty)	1' 1 1/16"	Well size, intermediate unit	53' x 102 3/8"
		* Loaded with two empty 9' 6 1/2" containers	
WEIGHT / CAPACITY (Estimated)		CURVE NEGOTIABILITY RADIUS	
Light weight	125,000 lbs.	Uncoupled, horizontal	180'
Gross rail load	485,000 lbs.	Uncoupled, vertical	1,250'
Capacity, net	360,000 lbs.	Coupled to like car	306'
Average capacity per well	120,000 lbs.	Coupled to 40' base car	302'
These general dimensions are representati			



## TECHNICAL BULLETIN DOUBLE-STACK CAR